

BILL OF QUANTITIES



Contract No: BCS-NA-2019~20/N-35/01
Location : KM 96+800 on N-35 (Butt Bridge)
Engineer Estimate (Cost) Rs. 1,994,925.00

Item No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
NSI-1	Repair/Rehabilitation of Bridge Deck Slab. Remove deteriorated Concrete Class-A3, Reinforcement of Grade 60 Bonding agent (Sikadur 32 or equivalent), hardening accelerator (Sika Rapid-1 or equivalent), Ensure wet curing for minimum 14 days with no traffic on the freshly laid pot holes, complete in all respect	SM	52.80	24,466.10	1,291,810.08
NSI-2	Maintain Smooth flow of Traffic by provision of Traffic Barriers. Delinators/Cones, Sign/ Warning boards, warning tapes and Three point men, one at a time in 3 shifts of 8 hrs each on 24/7 basis. If any mishap or accident happens due to the negligence in traffic management, then it will be the responsibility of the contractor (Complete in all respect)	LS	1.00	400,000.00	400,000.00
NSI-3	Structural Steel for steel channels welded on the surface of steel girders at 500mm c/c in specified in drawings (including welding, cutting and placement) complete in all respect.	Kg	14.63	213.00	3115.19
NSI-4	Repair of Damaged side railing and footpath using Concrete Class-A1 (Complete in all respect)	LS	1.00	300,000.00	300,000.00
Total: (Rs.)					1,994,925.00

% Above _____ Rs. _____

% Below _____ Rs. _____

Total Bid Cost Rs. _____

Rupees in word _____

Signatures/Stamp of Contractor's: _____

Secretary

Member

Member

Member

Chairman

DD (Maint)
NHA, Atd

Dir (Coord) NZ
Peshawar

Dir/DD(M&I)
NA's Region

DD (Acct) NAs
Abbottabad

Dir (Maint) NA's
NHA, Atd